



DIAPHRAGMS: Erect the diaphragms the same day that the precast beams are placed on the substructure. Include the cost of all materials and labor required to fabricate and erect the diaphragms in the bid for Precast Beams.



SUBMITTED Bart Cohen 02-26-20
DIRECTOR DIVISION OF STRUCTURAL DESIGN
DATE

APPROVED [Signature] 02-26-20
STATE HIGHWAY ENGINEER
DATE