R2-10

R2-11



8" (MIN.) FY

S4-4P

8" (MIN.) FY

REVISION DATE: 08/11/2026
REVISION NUMBER: 1

08/11/2026
DATE
SUBMITTED
DIVISION DIRECTOR

DATE
APPROVED
STATE HIGHWAY ENGINEER

TEMPORARY

APPLICATION

IN ACCORDANCE WITH KRS 189.2327, IN ORDER FOR HIGHER FINES TO BE ESTABLISHED IN A HIGHWAY WORK ZONE, SIGNS INFORMING DRIVERS OF THE WORK ZONE AND THAT FINES ARE HIGHER MUST BE DISPLAYED AND AT LEAST ONE (1) BONA FIDE WORKER MUST BE PRESENT.

THE ENGINEER MAY DETERMINE WHETHER TO ESTABLISH A HIGHER FINES ZONE WITHIN A HIGHWAY WORK ZONE BASED ON ENGINEERING JUDGMENT.

~ NOTES ~

1. *THE BEGIN AND END HIGHER FINES ZONE SIGNS SHALL BE 36" X 48" FOR FREEWAYS AND EXPRESSWAYS AND 24" X 30" FOR OTHER ROADWAYS. "WHEN FLASHING" PLAQUES SHALL BE 36" X 18" FOR FREEWAYS EXPRESSWAYS AND 24" X 12" FOR OTHER ROADWAYS.*
2. *SIGNS SHALL HAVE A WHITE BACKGROUND WITH A BLACK LEGEND AND SHALL BE MOUNTED AT ELEVATIONS AND OFFSETS PRESCRIBED IN THE MUTCD.*
3. *USE ENGINEERING JUDGMENT WHEN DETERMINING THE LIMITS OF HIGHER FINES ZONES. FOR SHORTER LENGTH PROJECTS WHERE WORK WILL OCCUR THROUGHOUT THE PROJECT LIMITS, LOCATE "BEGIN HIGHER FINES ZONE" SIGN BETWEEN THE SECOND AND THIRD ADVANCE WARNING SIGN AND LOCATE THE "END HIGHER FINES ZONE" SIGN 250' IN ADVANCE OF THE "END ROAD WORK" SIGN. FOR LONGER LENGTH PROJECTS WHERE WORK WILL NOT OCCUR THROUGHOUT THE PROJECT LIMITS, CONSIDER PLACING SIGNS ONLY IN AREAS WHERE ACTIVITY IS OCCURRING. REFER TO SHEET 004 FOR ADDITIONAL INFROMATION REGARDING RECOMMENDED LOCATIONS OF HIGHER FINES IN RELATION TO OTHER WORK ZONE SIGNING.*
4. *SIGNS SHALL BE DUAL-MOUNTED ON MULTI-LANE HIGHWAYS WHERE MEDIAN IS WIDE ENOUGH TO MAINTAIN LATERAL CLEARANCES AS PRESCRIBED IN THE MUTCD. WHERE CONSTRUCTION ONLY AFFECTS ONE DIRECTION OF A DIVIDED HIGHWAY WITH A BARRIER OR WIDE MEDIAN, SIGNS SHALL NOT BE ERECTED FOR OPPOSING DIRECTION.*
5. *ADDITIONAL SIGNS MAY BE REQUIRED FOR LONG HIGHWAY WORK ZONES OR WHERE RAMPS OR INTERSECTING STREETS JUNCTION WITHIN THE PROJECT LIMITS.*
6. *"BEGIN HIGHER FINES ZONE" SIGN ASSEMBLIES MAY INCLUDE A "WHEN FLASHING" PLAQUE AND FLASHING BEACONS. BEACONS SHALL BE YELLOW, AT LEAST 8" IN DIAMETER, AND MOUNTED HORIZONTALLY NEAR THE TOP OF THE SIGN ASSEMBLY. BEACONS SHALL FLASH ALTERNATELY AND CONFORM TO PART 4S OF THE MUTCD.*
7. *HIGHER FINES ZONES SIGNS SHALL BE COVERED IF A BONA FIDE WORKER WILL NOT BE PRESENT FOR A SIGNIFICANT PERIOD OF TIME. IN SUCH CASES, ASSEMBLIES WITH FLASHING BEACONS SHALL BE TURNED OFF.*

BID ITEMS AND UNITS TO BID

TEMPORARY SIGNS	*SQFT*	*WHEN APPLICABLE, USE WITH SHEETS 001, 003, AND 004.*